

**ADDENDUM NO. 2  
TO THE BIDDING /CONTRACT DOCUMENTS AND SPECIFICATIONS  
CITY OF HOLLY HILL  
CRA LIFT STATIONS #8, #11A AND #28 IMPROVEMENTS  
BID NO. 11-CO-02**

**February 16, 2012**

To All Plan Holders:

The following changes, clarifications and additions are hereby made part of the bidding and project specifications for the above referenced project dated January 2012 and prepared by Quentin L. Hampton Associates, Inc. as fully and completely as if the same were fully set forth therein.

1. **Specification Section 11320 'Collection System Submersible Pumps' -**  
Spare parts to include one (1) additional pump controller and one (1) transducer simulator for programming spare controller.
2. **Plan Sheets 4, 6, and 8 - Lift Station Equipment:**
  - Check valves to be lever weighted, no cushioning required.
3. **Plan Sheets 5 - Lift Station 11A Site Plan and Profile:**
  - Force main fittings to be ductile iron mechanical joint, epoxy lined.
  - HDPE pipe to have fused mechanical adapters at fittings. No inserts accepted.
  - HDPE pipe to be DIPS.
4. **The bid due date and time remains unchanged.**

**Disclaimer: This addendum was sent via e-mail. The delivery confirmation is acknowledgement that the addendum has been received. It is the sole responsibility of the bidder to confirm that all addenda have been received prior to submitting bid and acknowledge such in the bid documents.**